



Real People. Real Solutions.

116 North Wilson Avenue  
PO Box 68  
Jefferson, IA 50129

Phone: (515) 766-4423  
Bolton-Menk.com

May 7, 2026

Board of Supervisors  
Worth County Courthouse  
1000 Central Ave  
Northwood, Iowa 50459

RE: Amendment No. 3 to the Engineer's Report  
Drainage District No. 18  
Project No.: 24X135030000

Dear Board Members:

**Open Ditch Permitting:**

In October of 2025, the district received a letter from the Army Corps of Engineers indicating that no stream mitigation permit is required for this drainage improvement project. That letter is attached to this amendment. This opens the possibility for construction of an open ditch improvement, which was discussed in Amendment No. 2.

At the informational meeting held in July of 2024, landowners mentioned the possibility of extending the open ditch only as far as Cardinal Avenue or 410<sup>th</sup> Street, in an effort to minimize the number of landowners whose land would be severed by the ditch.

With an open ditch being a feasible option that does not require a stream mitigation permit, we wish to add an option which includes extending the open ditch to Cardinal Ave. and installation of a main tile upstream of the ditch.

The estimated total cost to construct the ditch and main tile with a ½" DC is \$1,758,000. A cost estimate breakdown is attached to this amendment which includes an estimated construction cost as well as estimates for purchasing right-of-way and severance payments to landowners whose land would be divided by the open ditch.

**Tile Capacity Analysis**

Drainage District No. 18 as a whole has limited contained surface storage. This means much of the runoff from rain events flows overland, while some is contained in naturally occurring potholes. An analysis was conducted to determine if larger drainage coefficients would have a major impact on the detention time of runoff in these potholes. Tables are attached to this amendment that show the results of this analysis.

The ½" DC is the standard accepted drainage coefficient, with larger coefficients only recommended when significant ponded storage requires a tile outlet to properly drain. For the three drainage coefficient options presented, only one pothole saw a significant reduction in detention time, while the other two potholes saw only minor differences.

Name: Amendment No. 3

Date: May 7, 2026

Page: 2

Days to Drain Potholes by DC			
DC	<sup>1</sup> Pothole 1	<sup>2</sup> Pothole 2	<sup>2</sup> Pothole 3
½"	4.52	0.36	0.36
¾"	3.21	0.24	0.24
1"	2.35	0.18	0.18

<sup>1</sup> Days to drain reflect a rainfall depth of 7.7". Days to drain a 3.1" rainfall range from 1.1 days to 2.1 days.

<sup>2</sup> Days to drain is the same for all storm events.

The revised open ditch option included in this amendment, along with the four options discussed previously in Amendment No. 2 will all provide the drainage improvement sought by the district. We recommend the ½" DC option presented in Amendment No. 2 due to the relatively small storage volume in the district.

Sincerely,

**Bolton & Menk, Inc.**



**Jon Rosengren, P.E.**

Project Manager

Attached:

Army Corps of Engineers Letter to the District

Project Cost Estimate

Pothole Locations Map

Overflow Analysis Tables



**DEPARTMENT OF THE ARMY**  
**CORPS OF ENGINEERS, ROCK ISLAND DISTRICT**  
**PO BOX 2004 CLOCK TOWER BUILDING**  
**ROCK ISLAND, ILLINOIS 61204-2004**

October 15, 2025

Regulatory Division

SUBJECT: CEMVR-RD-2024-1074

Mr. Colton Cummingham  
Water Resource Design Engineer  
Bolton and Menk, Inc.  
430 E. Grand Avenue, Suite 101  
Des Moines, IA 50309

Dear Mr. Colton Cummingham:

Our office has reviewed your application received on September 24, 2024, concerning the proposed DD 18 Proposed Open Ditch located in Section 32, Township 99 North, Range 22 West, Worth County, Iowa 43.3570372, -93.4606024.

We have determined that your project, as proposed, is a non-regulated activity and does not require a Department of the Army (DA) permit under Section 404 of the Clean Water Act. The decision regarding this action is based on information found in the administrative record which documents the District's decision-making process, the basis for the decision, and the final decision.

You are advised that this determination for your project is valid for five years from the date of this letter. If the project is not completed within this five-year period or your project plans change, you should contact our office for another determination.

Although a DA permit will not be required for the project, this does not eliminate the requirement that you must still acquire other applicable Federal, state, and local permits.

The Rock Island District Regulatory Division is committed to providing quality and timely service to our customers. In an effort to improve customer service, please take a moment to complete our Customer Service Survey found on our web site at <https://regulatory.ops.usace.army.mil/ords/f?p=136:4> (be sure to select "Rock Island District" under the area entitled: Which Corps office did you deal with?).

Should you have any questions, please contact our Regulatory Division by letter, email [Jeffrey.e.nelson@usace.army.mil](mailto:Jeffrey.e.nelson@usace.army.mil), or telephone Jeff Nelson at 309/216-5036.

- 2 -

Sincerely,

A handwritten signature in black ink that reads "Jeff Nelson" with a long horizontal flourish extending to the right.

Jeff Nelson  
Eastern Branch  
Regulatory Division

Enclosures

cc:

[section401wqc@dnr.iowa.gov](mailto:section401wqc@dnr.iowa.gov)

# ENGINEER'S ESTIMATE

DRAINAGE REPAIRS- OPEN DITCH  
DRAINAGE DISTRICT NO. 18  
DALLAS COUNTY, IOWA  
BMI PROJECT NO. 24X135030000



Real People. Real Solutions.

Date: 5/7/2026

Item No.	Item	Estimated Quantity	Unit	Unit Price	Total Amount
----------	------	--------------------	------	------------	--------------

NOTE: COUNTY ROAD, UTILITY AND RAILROAD COSTS HAVE NOT BEEN CALCULATED FOR THIS TIME.

## CONSTRUCTION DIVISION 1 - DD 18 MAIN OPEN DITCH CONSTRUCTION - END AT CARDINAL AVE

101	EXCAVATION	53,000	CY	\$3.00	\$159,000.00
102	TOPSOIL STRIPPING	8,000	CY	\$4.00	\$32,000.00
103	SPOIL LEVELING (BOTH SIDES)	49	STA	\$300.00	\$14,700.00
104	DAILY SEED & FERTILIZE BANKS	49	STA	\$100.00	\$4,900.00
105	SPOIL TILLAGE AND ROCK PICK-UP	49	STA	\$50.00	\$2,450.00
106	SPOIL TEMPORARY SEEDING	49	STA	\$80.00	\$3,920.00
107	TILE EXTENSION, 12" CMP	360	LF	\$30.00	\$10,800.00
108	TILE EXTENSION, 15" CMP	60	LF	\$35.00	\$2,100.00
109	TILE EXTENSION, 18" CMP	20	LF	\$45.00	\$900.00
110	SURFACE DRAIN, 18" CMP	360	LF	\$60.00	\$21,600.00
111	SURFACE DRAIN, 24" CMP	40	LF	\$75.00	\$3,000.00
112	RIPRAP, CLASS D	180	TN	\$65.00	\$11,700.00
113	EROSION MANAGEMENT PLAN	1	LS	\$1,000.00	\$1,000.00
114	SILT FENCE	100	LF	\$3.00	\$300.00
115	FENCE CUTS	2	EA	\$250.00	\$500.00
116	TILE OUTLET MODIFICATIONS	12	EA	\$250.00	\$3,000.00
117	MOBILIZATION	1	LS	\$15,700.00	\$15,700.00
					<b>\$287,570.00</b>

## CONSTRUCTION DIVISION 2 - DD 18 OPEN DITCH REPAIR

201	EXCAVATION	12	STA	\$250.00	\$3,000.00
202	SPOIL LEVELING (BOTH SIDES)	12	STA	\$200.00	\$2,400.00
203	DAILY SEED & FERTILIZE BANKS	12	STA	\$100.00	\$1,200.00
204	SPOIL TILLAGE AND ROCK PICK-UP	12	STA	\$30.00	\$360.00
205	SPOIL TEMPORARY SEEDING	12	STA	\$80.00	\$960.00
206	ADMINISTRATION OF EROSION MANAGEMENT PLAN	1	LS	\$1,000.00	\$1,000.00
207	SILT FENCE	100	LF	\$3.00	\$300.00
208	MOBILIZATION	1	LS	\$500.00	\$500.00

## CONSTRUCTION DIVISION 3 - DD 18 OPEN MAIN TILE IMPROVEMENT

301	2000D R.C.P. 18" DIA.	525	LF	\$42.00	\$22,050.00
302	2000D R.C.P. 24" DIA.	2,500	LF	\$47.00	\$117,500.00

Item No.	Item	Estimated Quantity	Unit	Unit Price	Total Amount
303	2000D R.C.P. 30" DIA.	3,100	LF	\$62.00	\$192,200.00
304	2000D R.C.P. 36" DIA.	2,500	LF	\$80.00	\$200,000.00
305	12" ON XX" DIA. R.C.P. TEE	17	EA	\$1,000.00	\$17,000.00
306	18" DIA. R.C.P. ELBOW SEC., FABRICATION	1	EA	\$600.00	\$600.00
307	24" DIA. R.C.P. ELBOW SEC., FABRICATION	3	EA	\$700.00	\$2,100.00
308	24" TO 18" DIA. R.C.P. REDUCER, FABRICATION	1	EA	\$1,200.00	\$1,200.00
309	BEEHIVE TILE INTAKES	2	EA	\$500.00	\$1,000.00
310	CRUSH EXISTING TILE	2,425	LF	\$5.00	\$12,125.00
311	LATERAL TILE CONNECTIONS, 10" DIA. OR SMALLER	10	EA	\$550.00	\$5,500.00
312	LATERAL TILE CONNECTIONS, 12" DIA. OR LARGER	2	EA	\$1,100.00	\$2,200.00
313	TILE TRENCH STABILIZATION & CRADLING ROCK	50	TN	\$30.00	\$1,500.00
314	ADMINISTRATION OF EROSION MANAGEMENT PLAN	1	LS	\$1,000.00	\$1,000.00
315	FENCE CUTS	1	EA	\$250.00	\$250.00
316	MOBILIZATION	1	LS	\$8,800.00	\$8,800.00
					<u>\$585,025.00</u>
				<b>ESTIMATED CONSTRUCTION COSTS TOTAL:</b>	<u><u>\$872,600.00</u></u>
				<b>CONSTRUCTION CONTINGENCY</b>	<u><u>\$43,600.00</u></u>

**ALTERNATIVE ADDITIONAL SEEDING METHODS**

401	HYDRAULIC MULCH SEEDING	61	STA	<u>\$300.00</u>	<u>\$18,300.00</u>
402	CONVENTIONAL MULCH SEEDING	61	STA	<u>\$300.00</u>	<u>\$18,300.00</u>

**Associated Project Costs**

DAMAGES	\$36,000.00
RIGHT-OF-WAY AND SEVERANCE	\$560,000.00

**Engineering**


SURVEY, STUDY & REPORT THOROUGH HEARINGS	<u>\$50,000.00</u>
PERMITS AND ENVIRONMENTAL COMPLIANCE	<u>\$10,000.00</u>
CONSTRUCTION PLANS, SPECIFICATIONS & BID LETTING	<u>\$15,000.00</u>
CONSTRUCTION ENGINEERING SERVICES	<u>\$35,000.00</u>
LEGAL SEVICES, PUBLICATIONS, MAILINGS, ETC.	<u>\$5,000.00</u>
FINANCE & INTEREST	<u>\$130,200.00</u>

**ESTIMATED ASSOCIATED PROJECT COSTS TOTAL: \$841,200.00**

**ESTIMATED PROJECT COST : \$1,757,400.00**

**TOTAL ESTIMATED COST ASSESSED TO LANDOWNERS : \$1,758,000.00**

Estimated Average Cost Per Benefited Acre (1,416 ac)	\$1,242
Estimated Average Cost Per Acre Per Year (10 years)	\$199
Estimated Average Cost Per Acre Per Year (20 years)	\$127



1/2" DC - Pothole 1									
WSHD					149.00 D <sub>c</sub>	0.56			
					D <sub>c</sub>	0.024			
Elev	ft <sup>2</sup>	Ac	Avg V (ac-ft)	Cum V (ac-ft)	D (in)	Q <sub>out</sub>	3.510		
1254.00	1454.00	0.03		0.00	0.00	7 Day Ac	#N/A		
1255.00	142215.00	3.26	1.65	1.65	0.13				
1256.00	316104.00	7.26	5.26	6.91	0.56				
1258.00	612908.00	14.07	24.59	26.24	2.11		ac-in	in	
			31.50				378.02	2.54	
Runoff AMC 1 Poorly Drained AMC Adjusted CN=78									
Return	Rain D	Runoff D	Overflow D <sub>in</sub>	Total D <sub>in</sub>	Full?	Elev	Overflow D <sub>o</sub>	Overflow V	Drain T
2.00	3.06	1.17		1.17	NO	1256.79	0.00	0.00	2.09
5.00	3.83	1.75		1.75	NO	1257.54	0.00	0.00	3.13
10.00	4.55	2.33		2.33	NO	1389.43	0.00	0.00	4.16
25.00	5.67	3.29		3.29	YES	Over	0.75	9.34	4.52
50.00	6.63	4.14		4.14	YES	Over	1.60	19.91	4.52
100.00	7.68	5.10		5.10	YES	Over	2.56	31.77	4.52

1/2" DC - Pothole 2									
WSHD					146.00 D <sub>c</sub>	0.68			
					D <sub>c</sub>	0.029			
Elev	ft <sup>2</sup>	Ac	Avg V (ac-ft)	Cum V (ac-ft)	D (in)	Q <sub>out</sub>	8.450		
1251.00	1338.00	0.03		0.00	0.00	7 Day Ac	#N/A		
1252.00	41290.00	0.95	0.49	0.49	0.04				
1253.00	95258.00	2.19	1.57	2.06	0.17				
1254.00	244572.00	5.61	3.90	5.96	0.48	5.84	ac-in	in	
			5.96				71.49	0.49	
Runoff AMC 1 Well Drained AMC Adjusted CN=70									
Return	Rain D	Runoff D	Overflow D <sub>in</sub>	Total D <sub>in</sub>	Full?	Elev	Overflow D <sub>o</sub>	Overflow V	Drain T
2.00	3.06	0.75		0.75	YES	Over	0.26	3.14	0.36
5.00	3.83	1.22		1.22	YES	Over	0.73	8.86	0.36
10.00	4.55	1.71		1.71	YES	Over	1.22	14.84	0.36
25.00	5.67	2.55	0.77	3.31	YES	Over	2.82	34.35	0.36
50.00	6.63	3.31		3.31	YES	Over	2.82	34.35	0.36
100.00	7.68	4.19		4.19	YES	Over	3.70	45.03	0.36

1/2" DC - Pothole 3									
WSHD					527.00 D <sub>c</sub>	0.44			
					D <sub>c</sub>	0.019			
Elev	ft <sup>2</sup>	Ac	Avg V (ac-ft)	Cum V (ac-ft)	D (in)	Q <sub>out</sub>	15.330		
1246.00	92730.00	2.13		0.00	0.00	7 Day Ac	#N/A		
1247.00	599007.00	13.75	7.94	7.94	0.64				
1248.00	968447.00	22.23	17.99	25.93	2.09				
1249.00	1247241.00	28.63	25.43	51.36	4.14	181.67	ac-in	in	
			51.36				616.37	1.17	
Runoff AMC 2 Poorly Drained CN=91									
Return	Rain D	Runoff D	Overflow D <sub>in</sub>	Total D <sub>in</sub>	Full?	Elev	Overflow D <sub>o</sub>	Overflow V	Drain T
2.00	3.06	2.13	0.07	2.20	YES	Over	1.71	20.79	0.36
5.00	3.83	2.85		2.85	YES	Over	2.37	28.78	0.36
10.00	4.55	3.55		3.55	YES	Over	3.06	37.19	0.36
25.00	5.67	4.63		4.63	YES	Over	4.14	50.43	0.36
50.00	6.63	5.57		5.57	YES	Over	5.09	61.87	0.36
100.00	7.68	6.61		6.61	YES	Over	6.12	74.45	0.36

3/4" DC - Pothole 1									
WSHD					149.00 D <sub>c</sub>	0.79			
					D <sub>c</sub>	0.033			
Elev	ft <sup>2</sup>	Ac	Avg V (ac-ft)	Cum V (ac-ft)	D (in)	Q <sub>out</sub>	7 Day Ac		
1254.00	1454.00	0.03		0.00	0.00	0.00	#N/A		
1255.00	142215.00	3.26	1.65	1.65	1.65	0.13			
1256.00	316104.00	7.26	5.26	6.91	6.91	0.56			
1258.00	612908.00	14.07	24.59	26.24	26.24	2.11		ac-in	in
			31.50					378.02	2.54
Runoff AMC 1 Poorly Drained AMC Adjusted CN=78									
Return	Rain D	Runoff D	Overflow D <sub>in</sub>	Total D <sub>in</sub>	Full?	Elev	Overflow D <sub>o</sub>	Overflow V	Drain T
	2.00	3.06	1.17		1.17 NO	1256.79	0.00	0.00	1.48
	5.00	3.83	1.75		1.75 NO	1257.54	0.00	0.00	2.22
	10.00	4.55	2.33		2.33 NO	1389.43	0.00	0.00	2.95
	25.00	5.67	3.29		3.29 YES	Over	0.75	9.34	3.21
	50.00	6.63	4.14		4.14 YES	Over	1.60	19.91	3.21
	100.00	7.68	5.10		5.10 YES	Over	2.56	31.77	3.21

3/4" DC - Pothole 2									
WSHD					146.00 D <sub>c</sub>	1.02			
					D <sub>c</sub>	0.043			
Elev	ft <sup>2</sup>	Ac	Avg V (ac-ft)	Cum V (ac-ft)	D (in)	Q <sub>out</sub>	7 Day Ac		
1251.00	1338.00	0.03		0.00	0.00	0.00	#N/A		
1252.00	41290.00	0.95	0.49	0.49	0.49	0.04			
1253.00	95258.00	2.19	1.57	2.06	2.06	0.17			
1254.00	244572.00	5.61	3.90	5.96	5.96	0.48	5.84	ac-in	in
			5.96					71.49	0.49
Runoff AMC 1 Well Drained AMC Adjusted CN=70									
Return	Rain D	Runoff D	Overflow D <sub>in</sub>	Total D <sub>in</sub>	Full?	Elev	Overflow D <sub>o</sub>	Overflow V	Drain T
	2.00	3.06	0.75		0.75 YES	Over	0.26	3.14	0.24
	5.00	3.83	1.22		1.22 YES	Over	0.73	8.86	0.24
	10.00	4.55	1.71		1.71 YES	Over	1.22	14.84	0.24
	25.00	5.67	2.55	0.77	3.31 YES	Over	2.82	34.35	0.24
	50.00	6.63	3.31		3.31 YES	Over	2.82	34.35	0.24
	100.00	7.68	4.19		4.19 YES	Over	3.70	45.03	0.24

3/4" DC - Pothole 3									
WSHD					527.00 D <sub>c</sub>	0.68			
					D <sub>c</sub>	0.029			
Elev	ft <sup>2</sup>	Ac	Avg V (ac-ft)	Cum V (ac-ft)	D (in)	Q <sub>out</sub>	7 Day Ac		
1246.00	92730.00	2.13		0.00	0.00	0.00	#N/A		
1247.00	599007.00	13.75	7.94	7.94	7.94	0.64			
1248.00	968447.00	22.23	17.99	25.93	25.93	2.09			
1249.00	1247241.00	28.63	25.43	51.36	51.36	4.14	181.67	ac-in	in
			51.36					616.37	1.17
Runoff AMC 2 Poorly Drained CN=91									
Return	Rain D	Runoff D	Overflow D <sub>in</sub>	Total D <sub>in</sub>	Full?	Elev	Overflow D <sub>o</sub>	Overflow V	Drain T
	2.00	3.06	2.13	0.07	2.20 YES	Over	1.71	20.79	0.24
	5.00	3.83	2.85		2.85 YES	Over	2.37	28.78	0.24
	10.00	4.55	3.55		3.55 YES	Over	3.06	37.19	0.24
	25.00	5.67	4.63		4.63 YES	Over	4.14	50.43	0.24
	50.00	6.63	5.57		5.57 YES	Over	5.09	61.87	0.24
	100.00	7.68	6.61		6.61 YES	Over	6.12	74.45	0.24

1" DC - Pothole 1									
WSHD					149.00 D <sub>c</sub>	1.08			
					D <sub>c</sub>	0.045			
Elev	ft <sup>2</sup>	Ac	Avg V (ac-ft)	Cum V (ac-ft)	D (in)	Q <sub>out</sub>	6.750		
1254.00	1454.00	0.03		0.00	0.00	7 Day Ac	#N/A		
1255.00	142215.00	3.26	1.65	1.65	0.13				
1256.00	316104.00	7.26	5.26	6.91	0.56				
1258.00	612908.00	14.07	24.59	26.24	2.11		ac-in	in	
			31.50				378.02	2.54	
Runoff AMC 1 Poorly Drained AMC Adjusted CN=78									
Return	Rain D	Runoff D	Overflow D <sub>in</sub>	Total D <sub>in</sub>	Full?	Elev	Overflow D <sub>o</sub>	Overflow V	Drain T
	2.00	3.06	1.17		1.17 NO	1256.79	0.00	0.00	1.09
	5.00	3.83	1.75		1.75 NO	1257.54	0.00	0.00	1.63
	10.00	4.55	2.33		2.33 NO	1389.43	0.00	0.00	2.16
	25.00	5.67	3.29		3.29 YES	Over	0.75	9.34	2.35
	50.00	6.63	4.14		4.14 YES	Over	1.60	19.91	2.35
	100.00	7.68	5.10		5.10 YES	Over	2.56	31.77	2.35

1" DC - Pothole 2									
WSHD					146.00 D <sub>c</sub>	1.35			
					D <sub>c</sub>	0.057			
Elev	ft <sup>2</sup>	Ac	Avg V (ac-ft)	Cum V (ac-ft)	D (in)	Q <sub>out</sub>	16.790		
1251.00	1338.00	0.03		0.00	0.00	7 Day Ac	#N/A		
1252.00	41290.00	0.95	0.49	0.49	0.04				
1253.00	95258.00	2.19	1.57	2.06	0.17				
1254.00	244572.00	5.61	3.90	5.96	0.48	5.84	ac-in	in	
			5.96				71.49	0.49	
Runoff AMC 1 Well Drained AMC Adjusted CN=70									
Return	Rain D	Runoff D	Overflow D <sub>in</sub>	Total D <sub>in</sub>	Full?	Elev	Overflow D <sub>o</sub>	Overflow V	Drain T
	2.00	3.06	0.75		0.75 YES	Over	0.26	3.14	0.18
	5.00	3.83	1.22		1.22 YES	Over	0.73	8.86	0.18
	10.00	4.55	1.71		1.71 YES	Over	1.22	14.84	0.18
	25.00	5.67	2.55	0.77	3.31 YES	Over	2.82	34.35	0.18
	50.00	6.63	3.31		3.31 YES	Over	2.82	34.35	0.18
	100.00	7.68	4.19		4.19 YES	Over	3.70	45.03	0.18

1" DC - Pothole 3									
WSHD					527.00 D <sub>c</sub>	0.91			
					D <sub>c</sub>	0.038			
Elev	ft <sup>2</sup>	Ac	Avg V (ac-ft)	Cum V (ac-ft)	D (in)	Q <sub>out</sub>	31.530		
1246.00	92730.00	2.13		0.00	0.00	7 Day Ac	#N/A		
1247.00	599007.00	13.75	7.94	7.94	0.64				
1248.00	968447.00	22.23	17.99	25.93	2.09				
1249.00	1247241.00	28.63	25.43	51.36	4.14	181.67	ac-in	in	
			51.36				616.37	1.17	
Runoff AMC 2 Poorly Drained CN=91									
Return	Rain D	Runoff D	Overflow D <sub>in</sub>	Total D <sub>in</sub>	Full?	Elev	Overflow D <sub>o</sub>	Overflow V	Drain T
	2.00	3.06	2.13	0.07	2.20 YES	Over	1.71	20.79	0.18
	5.00	3.83	2.85		2.85 YES	Over	2.37	28.78	0.18
	10.00	4.55	3.55		3.55 YES	Over	3.06	37.19	0.18
	25.00	5.67	4.63		4.63 YES	Over	4.14	50.43	0.18
	50.00	6.63	5.57		5.57 YES	Over	5.09	61.87	0.18
	100.00	7.68	6.61		6.61 YES	Over	6.12	74.45	0.18